

ಚಾಮುಂಡೇಶ್ವರಿ ವಿದ್ಯುತ್ ಸರಬರಾಜು ನಿಗಮ ನಿಯಮಿತ

(ಕರ್ನಾಟಕ ಸರ್ಕಾರದ ಸ್ವಾಮ್ಯದ ಒಳಪಟ್ಟಿದೆ)

ಚಾವಿ ಸಿನಿ.

ಉಪವಿಭಾಗ



CHAMUNDESWARI ELECTRICITY  
SUPPLY CORPORATION LTD

(A Govt. of Karnataka undertaking)

CESC, Virajpet subdivision

Web Site : <https://cescmysore.karnataka.gov.in/>

RECOMMENDATION FORM FOR AWARDING WORK ON LABOUR CONTRACT

To,  
Executive Engineer(Ele),  
O&M division CESC,  
Madikeri Division

Sir,

Sub : Awarding of work on labor contract basis

Ref : 06

Ref Date: 05/10/2022

I Wish to recommend for awarding the works detailed here under in favour of **Anand Electricals177/1 Navoor House, Amogha Behind KSRTC Bus Stand, Navoor, Sulia-574239 ICL157686MNG** on labour contract basis as per standard terms and conditions of the Board.

Name of the Work : Replacement and Maintanance  
WorkOrder No : C-3091 / 3233122230081 dated 26/08/2022  
Work Account Code : 74.5107

Estimate Part: A		Estimate Part Description : EXTENTION OF 11KV LINE						
Sl. no	Item Code	Item Name	UOM	Quantity	Labour Charges	Total Labour Charges	Load/unload qty	Load/unload charge
1	279020	11kV Horizontal X Arms - Mild Steel (MS)	No	1.00	122.00	122.00	1.00	0.00
2	91050200	Fixing of 4 Pin cross arm with Insulator and Braces	each	2.00	28.00	56.00	2.00	0.00
3	91050200	Fixing of 4 Pin cross arm with Insulator and Braces	each	2.00	122.00	244.00	2.00	0.00
4	91051000	Fixing of GUY Set with break insulator making use of 7/3.15 mm (7/10 SWG) galvanised steel wire with turn buckle and anchoring arrangement as per approved	Per Set	3.00	201.00	603.00	3.00	0.00
5	91050300	Fixing of V-Shape/Horizontal cross arm including Single Top Support Brace and Insulator	each	3.00	122.00	366.00	3.00	0.00
6	91210300	For Transporting one pole from 105 to 185 Mtrs by Head Load where ever there is no accessibility for transporation by vehicle	per pole	4.00	235.00	940.00	4.00	0.00
7	279092	HT ST Support 50x6mm Flat - MS	No	1.00	81.00	81.00	1.00	0.00

8	91260200	Loading and unloading of 9 mtr RCC PSCC poles (loading of poles to vehicles at stores and unloading at worksnot)	No	3.00	106.00	318.00	3.00	0.00
9	200006	PSC Pole - 9 Mtr Long- 200 Kg WL	No	3.00	1,341.00	4,023.00	3.00	0.00
10	91131100	Releasing and Refixing of over head service mains (single phase three phase) for consumer installation and street lighting and similar work (While replacin	ction i	2.00	75.00	150.00	2.00	0.00
11	91050201	Releasing of 4 Pin cross arm along with Insulator and Braces	Each	2.00	109.80	219.60	2.00	0.00
12	91060500	Releasing of Rabbit Conductor	r km w	0.79	2,969.00	2,330.67	0.79	0.00
13	91050301	Releasing of V-Shape/Horizontal cross arm along with Single Top Support Brace and Insulator	Each	3.00	109.80	329.40	3.00	0.00
14	91060400	Releasing of Weasel Conductor	r km w	0.65	2,178.00	1,415.70	0.65	0.00
15	91060200	Stringing of Rabbit Conductor including pin binding providing jumps dead ending etc	r km w	0.75	3,959.00	2,969.25	0.75	0.00
16	91060100	Stringing of Weasel Conductor including pin binding providing jumps dead ending etc	r KM/W	0.65	2,905.00	1,888.25	0.65	0.00
17	284105	Weasel ACSR	Km	0.03	2,420.00	60.50	0.03	0.00
<b>Sub Total</b>					<b>16,116.37</b>			

<b>Total Labour Charge :</b>	
------------------------------	--

<b>16,116.37</b>
------------------

ESI & PF 17.75% of Labour & loc.Allw	:	2,860.65
CGST 09% of Labour & locality	:	1,450.47
SGST 09% of Labour & locality	:	1,450.47
<b>Total Labour Charges</b>	:	<b>5,761.60</b>

Special Locality Charges	:	7252.36
Break Down Charges	:	4,029.09
Additional Labour Charges 10% of Total LabourCharges)	:	0.00
Calamity Charges( 45% of Total Labour Charges)	:	0.00
Head Load Charges	:	0
<b>Total Other Labour Charges</b>	:	<b>11,281.45</b>
<b>Grand Total</b>	:	<b>33,159.42</b>

Grand Total in words	:	RUPEES THIRTY-THREE THOUSAND ONE HUNDRED FIFTY-NINE ONLY
----------------------	---	--

ESI Account No	:	77000384770000905
EMD Reciept Date	:	18/12/2010
EPF Account No	:	0038545000
EMD Reciept No	:	39767
EMD Amount	:	5,000.00

*[Signature]*  
Asst Executive Engineer(Elg),  
O&M Sub division CESC,  
Virajpet

*[Signature]*  
Junior/Asst Engineer(Elg),  
O&M Section,  
VIRAJPET