

ಚಾಮುಂಡೇಶ್ವರಿ ವಿದ್ಯುತ್ ಸರಬರಾಜು ನಿಗಮ ನಿಯಮಿತ

(ಕರ್ನಾಟಕ ಸರ್ಕಾರದ ಸ್ವಾಮ್ಯಕ್ಕೆ ಒಳಪಟ್ಟಿದೆ)

ಚಾ.ವಿ.ಸ.ನಿ.

ಉಪವಿಭಾಗ



CHAMUNDESWARI ELECTRICITY
SUPPLY CORPORATION LTD

(A Govt. of Karnataka undertaking)

CESC, Virajpet subdivision

Web Site : <https://cescmysore.karnataka.gov.in/>

RECOMMENDATION FORM FOR AWARDING WORK ON LABOUR CONTRACT

To,
Executive Engineer(Ele),
O&M division CESC,
Madikeri Division

Sir,

Sub : Awarding of work on labor contract basis

Ref : 02

Ref Date: 05/10/2022

I Wish to recommend for awarding the works detailed here under in favour of **Anand Electricals177/1 Navoor House, Amogha Behind KSRTC Bus Stand, Navoor, Sulia-574239 ICL157686MNG** on labour contract basis as per standard terms and conditions of the Board.

Name of the Work : Replacement and Maintainance
WorkOrder No : C-3100 / 3233122230070 dated 26/08/2022
Work Account Code : 74.5107

Estimate Part: A		Estimate Part Description : EXTENTION OF 11KV LINE						
Sl. no	Item Code	Item Name	UOM	Quantity	Labour Charges	Total Labour Charges	Load/unload qty	Load/unload charge
1	279020	11kv Horizontal X Arms - Mild Steel (MS)	No	2.00	122.00	244.00	2.00	0.00
2	91020400	Erection of RCC PSC poles 9 to 10 mtr long but in a pit of 1 8 mtr depth	No	3.00	1,377.00	4,131.00	3.00	0.00
3	91051000	Fixing of GUY Set with break insulator making use of 7/3.15 mm (7/10 SWG) galvanised steel wire with turn buckle and anchoring arrangement as per approved	Per Set	3.00	201.00	603.00	3.00	0.00
4	91050300	Fixing of V-Shape/Horizontal cross arm including Single Top Support Brace and Insulator	each	1.00	122.00	122.00	1.00	0.00
5	279092	HT ST Support 50x6mm Flat - MS	No	2.00	81.00	162.00	2.00	0.00
6	91260200	Loading and unloading of 9 mtr RCC PSCC poles (loading of poles to vehicles at stores and unloading at worksnot)	No	1.00	106.00	106.00	1.00	0.00
7	200006	PSC Pole - 9 Mtr Long- 200 Kg WL	No	1.00	1,341.00	1,341.00	1.00	0.00

8	284108	Rabbit ACSR	Km	0.02	3,299.00	49.49	0.02	0.00	
9	91060500	Releasing of Rabbit Conductor	r km w	1.20	2,969.00	3,562.80	1.20	0.00	
10	91020201	Releasing of RCC/PSCC Pole of 9 to 10 Mtr long in a pit of 1.8 Mtr depth	No	3.00	777.00	2,331.00	3.00	0.00	
11	91050301	Releasing of V-Shape/Horizontal cross arm along with Single Top Support Brace and Insulator	Each	1.00	109.80	109.80	1.00	0.00	
12	91160209	Straightening of slant bent poles RCC Pole 9 Mtr PSCC Pole with working load of 300Kg	No	6.00	563.00	3,378.00	6.00	0.00	
13	91060200	Stringing of Rabbit Conductor including pin binding providing jumps dead ending etc	r km w	1.20	3,959.00	4,750.80	1.20	0.00	
Sub Total					20,890.89				

Total Labour Charge :	20,890.89
------------------------------	------------------

ESI & PF 17.75% of Labour & loc.Allw	:	3,708.13
CGST 09% of Labour & locality	:	1,880.18
SGST 09% of Labour & locality	:	1,880.18
Total Labour Charges	:	7,468.49

Special Locality Charges	:	9400.90
Break Down Charges	:	5,222.72
Additional Labour Charges 10% of Total LabourCharges)	:	0.00
Calamity Charges(45% of Total Labour Charges)	:	0.00
Head Load Charges	:	0
Total Other Labour Charges	:	14,623.62
Grand Total	:	42,983.00

Grand Total in words	:	RUPEES FORTY-TWO THOUSAND NINE HUNDRED EIGHTY-THREE ONLY
-----------------------------	---	---

ESI Account No :	77000384770000905
EMD Receipt Date :	18/12/2010
EPF Account No :	0038545000
EMD Receipt No :	39767
EMD Amount :	5,000.00

[Handwritten signature]

Asst Executive Engineer(Ele),
O&M Sub division CESC,
Virajpet

[Handwritten signature]
Junior/Asst Engineer(Ele),
O&M Section,
VIRAJPET