



CHIAMUNDESWARI ELECTRICITY
SUPPLY CORPORATION LTD

(A Govt. of Karnataka undertaking)

CESC, Virajpet subdivision

Web Site : <http://cescmysore.karnataka.gov.in/>

RECOMMENDATION FORM FOR AWARDING WORK ON LABOUR CONTRACT

To,
Executive Engineer(Elc),
O&M division CESC,
Madikeri Division

Sir,

Sub : Awarding of work on labor contract basis

Ref : 03

Ref Date: 05/10/2022

I Wish to recommend for awarding the works detailed here under in favour of **Anand Electricals177/1 Navoor House, Amogha Behind KSRTC Bus Stand, Navoor, Sulia-574239 ICL157686MNG** on labour contract basis as per standard terms and conditions of the Board.

Name of the Work : Replacement and Maintanance
WorkOrder No : C-3102 / 3233122230068 dated 26/08/2022
Work Account Code : 74.5107

Estimate Part: A		Estimate Part Description : EXTENTION OF LT LINE						
Sl. no	Item Code	Item Name	UOM	Quantity	Labour Charges	Total Labour Charges	Load/unload qty	Load/unload charge
1	279020	11kv Horizontal X Arms - Mild Steel (MS)	No	2.00	122.00	244.00	2.00	0.00
2	279140	Anchor Rod using 12mm rounds/Guy Rod - MS	No	1.00	448.00	448.00	1.00	0.00
3	91020400	Erection of RCC PSC poles 9 to 10 mtr long but in a pit of 1.8 mtr depth	No	2.00	1,377.00	2,754.00	2.00	0.00
4	91050200	Fixing of 4 Pin cross arm with Insulator and Braces	each	4.00	28.00	112.00	4.00	0.00
5	91050200	Fixing of 4 Pin cross arm with Insulator and Braces	each	4.00	122.00	488.00	4.00	0.00
6	91051000	Fixing of GUY Set with break insulator making use of 7/3.15 mm (7/10 SWG) galvanised steel wire with turn buckle and anchoring arrangement as per approved	Per Set	1.00	201.00	201.00	1.00	0.00
7	279092	HT ST Support 50x6mm Flat - MS	No	2.00	81.00	162.00	2.00	0.00

-3102 / 3233122230068 dated 26/08/2022

Page 1 of 3



8	91260200	Loading and unloading of 9 mtr RCC PSCC poles (loading of poles to vehicles at stores and unloading at worksmn)	No	5.00	106.00	530.00
9	200006	PSC Pole - 9 Mtr Long- 200 Kg WL	No	5.00	1,341.00	6,705.00
10	91050201	Releasing of 4 Pin cross arm along with Insulator and Braces	Each	4.00	109.80	439.20
11	91051001	Releasing of GUY Set with break insulator 7/3.15 mm (7/10 SWG) galvanised steel wire turn buckle and anchoring arrangement Excluding excavation of PIT	Per Set	1.00	180.90	180.90
12	91020201	Releasing of RCC/PSCC Pole of 9 to 10 Mtr long in a pit of 1.8 Mtr depth	No	2.00	777.00	1,554.00
13	91060400	Releasing of Weasel Conductor	Per km w	1.38	2,178.00	3,005.64
14	91060100	Stringing of Weasel Conductor including pin binding providing jumps dead ending etc	Per KMM	1.38	2,905.00	4,008.90
15	284105	Weasel ACSR	Km	0.01	2,420.00	24.20
Sub Total					20,856.84	20,856.84

Total Labour Charge : 20,856.84

SI & PF 17.75% of Labour & loc.AI
 GST 09% of Labour & locality
 GST 09% of Labour & locality
 Total Labour Charges
 Special Locality Charges
 Break Down Charges
 Additional Labour Charge
 Labour Charges (45%
 Penalty Charges (45%
 Lead Load Charges
 Total Other Labour
 Grand Total
 Grand Total in w

ESI & PF 17.75% of Labour & loc.Allw	:	3,702.09
CGST 09% of Labour & locality	:	1,877.12
SGST 09% of Labour & locality	:	1,877.12
Total Labour Charges	:	7,456.32

Special Locality Charges	:	9385.58
Break Down Charges	:	5,214.21
Additional Labour Charges 10% of Total LabourCharges)	:	0.00
Calamity Charges(45% of Total Labour Charges)	:	0.00
Head Load Charges	:	0
Total Other Labour Charges	:	14,599.79
Grand Total	:	42,912.95

Grand Total in words : RUPEES FORTY-TWO THOUSAND NINE HUNDRED THIRTEEN ONLY

ESI Account No	:	77000384770000905
EMD Reciept Date	:	18/12/2010
EPF Account No	:	0038545000
EMD Reciept No	:	39767
EMD Amount	:	5,000.00

[Signature]
Asst Executive Engineer (Ele),
O&M Sub division CESC,
Virajpet

[Signature]
Junior/Asst Engineer (Ele),
O&M Section,
VIRAJPET