

ಚಾಮುಂಡೇಶ್ವರಿ ವಿದ್ಯುತ್ ಸರಬರಾಜು ನಿಗಮ ನಿಯಮಿತ

(ಕರ್ನಾಟಕ ಸರ್ಕಾರದ ಸ್ವಾಮ್ಯಕ್ಕೆ ಒಳಪಟ್ಟಿದೆ)

ಚಾ.ವಿ.ಸ.ನಿ.ನಿ.

ಉಪವಿಭಾಗ



CHAMUNDESWARI ELECTRICITY
SUPPLY CORPORATION LTD

(A Govt. of Karnataka undertaking)

CESC, Virajpet subdivision

Web Site : <https://cescmysore.karnataka.gov.in/>

RECOMMENDATION FORM FOR AWARDING WORK ON LABOUR CONTRACT

To,
Executive Engineer(Ele),
O&M division CESC,
Madikeri Division

Sir,

Sub : Awarding of work on labor contract basis

Ref : 4

Ref Date: 05/10/2022

I Wish to recommend for awarding the works detailed here under in favour of **Anand Electricals177/1 Navoor House, Amogha Behind KSRTC Bus Stand, Navoor, Sulia-574239 ICL157686MNG** on labour contract basis as per standard terms and conditions of the Board.

Name of the Work : Replacement and Maintanance
WorkOrder No : C-3103 / 3233122230067 dated 26/08/2022
Work Account Code : 74.5107

Estimate Part: A		Estimate Part Description : EXTENSION OF LT LINE						
Sl. no	Item Code	Item Name	UOM	Quantity	Labour Charges	Total Labour Charges	Load/unload qty	Load/unload charge
1	91050200	Fixing of 4 Pin cross arm with Insulator and Braces	each	3.00	28.00	84.00	3.00	0.00
2	91050200	Fixing of 4 Pin cross arm with Insulator and Braces	each	3.00	122.00	366.00	3.00	0.00
3	91051000	Fixing of GUY Set with break insulator making use of 7/3.15 mm (7/10 SWG) galvanised steel wire with turn buckle and anchoring arrangement as per approved	Per Set	1.00	201.00	201.00	1.00	0.00
4	91260200	Loading and unloading of 9 mtr RCC PSCC poles (loading of poles to vehicles at stores and unloading at worksnot)	No	2.00	106.00	212.00	2.00	0.00
5	200006	PSC Pole - 9 Mtr Long- 200 Kg WL	No	2.00	1,341.00	2,682.00	2.00	0.00
6	91050201	Releasing of 4 Pin cross arm along with Insulator and Braces	Each	3.00	109.80	329.40	3.00	0.00
7	91051001	Releasing of GUY Set with break insulator 7/3.15 mm (7/10 SWG) galvanised steel wire turn buckle and anchoring arrangement Excluding excavation of PIT	Per Set	1.00	180.90	180.90	1.00	0.00

8	91020201	Releasing of RCC/PSCC Pole of 9 to 10 Mtr long in a pit of 1.8 Mtr depth	No	1.00	777.00	777.00	1.00	0.00	
9	91060400	Releasing of Weasel Conductor	r km w	0.86	2,178.00	1,873.08	0.86	0.00	
10	91160201	Straightening of slant bent poles RCC Pole - 9 Mtr Long 150 Kg WL Sq Section	No	2.00	563.00	1,126.00	2.00	0.00	
11	91060100	Stringing of Weasel Conductor including pin binding providing jumps dead ending etc	r KMM	0.86	2,905.00	2,498.30	0.86	0.00	
12	284105	Weasel ACSR	Km	0.01	2,420.00	24.20	0.01	0.00	
Sub Total					10,353.88				


Total Labour Charge :	10,353.88
------------------------------	------------------


ESI & PF 17.75% of Labour & loc.Allw	:	1,837.81
CGST 09% of Labour & locality	:	931.85
SGST 09% of Labour & locality	:	931.85
Total Labour Charges	:	3,701.51

Special Locality Charges	:	4659.25
Break Down Charges	:	2,588.47
Additional Labour Charges 10% of Total LabourCharges)	:	0.00
Calamity Charges(45% of Total Labour Charges)	:	0.00
Head Load Charges	:	0
Total Other Labour Charges	:	7,247.72
Grand Total		21,303.11

Grand Total in words	:	RUPEES TWENTY-ONE THOUSAND THREE HUNDRED THREE ONLY
-----------------------------	---	--

ESI Account No	:	77000384770000905
EMD Reciept Date	:	18/12/2010
EPF Account No	:	0038545000
EMD Reciept No	:	39767
EMD Amount	:	5,000.00


Asst Executive Engineer(Ele),
O&M Sub division CESC,
Virajpet


Junior/Asst Engineer(Ele),
O&M Section,
VIRAJPET
