



RECOMMENDATION FORM FOR AWARDING WORK ON LABOUR CONTRACT

To,

Executive Engineer(Ele),
O&M division CESC,
Channarayapatna Division

Sir,

Sub : Awarding of work on labor contract basis

Ref : 3960-63

Ref Date: 12/09/2022

I Wish to recommend for awarding the works detailed here under in favour of **M/s Spurthi ElectricalsNambihally (V), Anekere (P), Dandiganahally (H), Channarayapatna. 1CL06460HSN** on labour contract basis as per standard terms and conditions of the Board.

Name of the Work : Service Connection

WorkOrder No : M-3608 / 3421322230023 dated 26/08/2022

Work Account Code : 14.4007

Estimate Part: A		Estimate Part Description : EXTENTION OF 11KV LINE						
Sl.no	Item Code	Item Name	UOM	Quantity	Labour Charges	Total Labour Charges	Load/unload qty	Load/unload charge
1	1270100	Loading of 25 kVA Transformer (when maintainance men for loading and unloading are not available in store)	No	1.00	205.00	205.00	1.00	0.00
2	304212	11kV 200Amps Single Break GOS	set	1.00	805.00	805.00	1.00	0.00
3	302122	11kV Class- HG Fuse Unit with Solid Core Insulators	Set	1.00	178.00	178.00	1.00	0.00
4	279020	11kV Horizontal X Arms - Mild Steel (MS)	No	2.00	122.00	244.00	2.00	0.00
5	280140	Anchor Rod using 12mm rounds/Guy Rod - GI	No	5.00	201.00	1,005.00	5.00	0.00
6	613050	Caution/Danger Board	No	1.00	61.00	61.00	1.00	0.00
7	1010802	d) Providing cement concrete to poles and Guy sets with material and labour including necessary curing etc. for Pole concretina with C.C. 1 2 4 (without	Each	4.00	200.00	800.00	4.00	0.00

8	321437	Distribution Transformer Stacked Core Open Bushing Type for 25kVA Aluminum Wdg Star 1(4 Star)	No	1.00	863.00	863.00	1.00	0.00	
9	279112	Double Pole TC Sets for erection of Transformer on RCC/PSC 9 Mtrs Long Poles For 25/63/100kVA 4/5 Star Rated Transformer using 9 Mtr Long RCC Pole	Set	1.00	2,623.00	2,623.00	1.00	0.00	
10	278911	GI Barbed wire (12mtrs/Kg)- Anticlimbing Device	Each	2.00	32.00	64.00	2.00	0.00	
11	279092	HT ST Support 50x6mm Flat - MS	No	2.00	81.00	162.00	2.00	0.00	
12	1260100	Loading and unloading of 8 mtr RCC PSCC poles (loading of poles to vehicles at stores and unloading at worksnot)	No	1.00	79.00	79.00	1.00	0.00	
13	1260200	Loading and unloading of 9 mtr RCC PSCC poles (loading of poles to vehicles at stores and unloading at worksnot)	No	2.00	106.00	212.00	2.00	0.00	
14	279014	LT 4 Pin X Arms - MS	No	2.00	122.00	244.00	2.00	0.00	
15	301107	LT Protection kit	No	1.00	260.00	260.00	1.00	0.00	
16	284503	LT Spacer for TC Wiring	No	8.00	52.00	416.00	8.00	0.00	
17	200004	PSC Pole - 8 Mtr Long- 200 Kg WL	No	1.00	1,072.00	1,072.00	1.00	0.00	
18	284108	Rabbit ACSR	Km	0.09	3,299.00	296.91	0.09	0.00	
19	200105	RCC Pole - 9 Mtr Long- 145 Kg WL	No	2.00	1,341.00	2,682.00	2.00	0.00	
20	200103	RCC Pole 8 Mtr Long 115 Kg	No	1.00	1,072.00	1,072.00	1.00	0.00	
21	1270600	Un loading of 25 kVA Transformer	No	1.00	205.00	205.00	1.00	0.00	
Sub Total					13,548.91				

Total Labour Charge :	13,548.91
------------------------------	------------------

ESI & PF 17.75% of Labour & loc.Allw	:	2,368.54
CGST 09% of Labour & locality	:	1,200.95
SGST 09% of Labour & locality	:	1,200.95
Total Labour Charges	:	4,770.45

Special Locality Charges	:	0
Break Down Charges	:	0.00
Additional Labour Charges 10% of Total LabourCharges)	:	0.00
Calamity Charges(45% of Total Labour Charges)	:	0.00
Head Load Charges	:	0
Total Other Labour Charges	:	0.00
Grand Total	:	18,114.36

Grand Total in words	:	RUPEES EIGHTEEN THOUSAND ONE HUNDRED FOURTEEN ONLY
-----------------------------	---	---

ESI Account No	:	KNCKR1358722
EMD Reciept Date	:	30/07/2015
EPF Account No	:	KNCKR1358722
EMD Reciept No	:	4211000256114
EMD Amount	:	5,000.00

Asst Executive Engineer(Ele),
O&M Sub division CESC,
Channarayapatna

Junior/Asst Engineer(Ele),
O&M Section,
UDAYAPURA