

ಚಾಮುಂಡೇಶ್ವರಿ ವಿದ್ಯುತ್ ಸರಬರಾಜು ನಿಗಮ ನಿಯಮಿತ

( ಕರ್ನಾಟಕ ಸರ್ಕಾರದ ಸ್ವಾಮ್ಯಕ್ಕೆ ಒಳಪಟ್ಟಿದೆ )

ಚಾ.ವಿ.ಸ.ನಿ.ನಿ.,

ಉಪವಿಭಾಗ



CHAMUNDESWARI ELECTRICITY  
SUPPLY CORPORATION LTD

(A Govt. of Karnataka undertaking )

CESC, Nuggihalli subdivision

Web Site : <https://cescmysore.karnataka.gov.in/>

RECOMMENDATION FORM FOR AWARDING WORK ON LABOUR CONTRACT

To,

Executive Engineer(Ele),  
O&M division CESC,  
Channarayapatna Division

Sir,

**Sub : Awarding of work on labor contract basis**

Ref : 1538

Ref Date: 04/11/2022

I Wish to recommend for awarding the works detailed here under in favour of **M/s Prema ElectricalsMIG-14, Housing Board, H.N.Pura Road, Adaguru (P), Channarayapatna-573116 1CL14452HSN** on labour contract basis as per standard terms and conditions of the Board.

**Name of the Work :** Extension and Improvement  
**WorkOrder No :** L-4273 / 3422322230059 dated 17/12/2021  
**Work Account Code :** 14.4307

Estimate Part: A		Estimate Part Description : EXTENTION OF 11KV LINE						
Sl. no	Item Code	Item Name	UOM	Quantity	Labour Charges	Total Labour Charges	Load/unload qty	Load/unload charge
1	279020	11kV Horizontal X Arms Mild Steel(MS)	No	5.00	106.00	530.00	5.00	0.00
2	279140	Anchor Rod using 12mm rounds/Guy Rod - MS	No	1.00	390.00	390.00	1.00	0.00
3	279092	HT ST Support 50x6mm Flat - MS	No	5.00	70.00	350.00	5.00	0.00
4	200006	PSC Pole - 9 Mtr Long- 200 Kg WL	No	1.00	1,166.00	1,166.00	1.00	0.00
5	284108	Rabbit ACSR	Km	0.37	2,869.00	1,067.27	0.37	0.00
6	200105	RCC Pole - 9 Mtr Long- 145 Kg WL	No	2.00	1,166.00	2,332.00	2.00	0.00
7	281683	Spiral Earth Electrode	No	3.00	61.00	183.00	3.00	0.00
<b>Sub Total</b>					<b>6,018.27</b>			

Estimate Part: B		Estimate Part Description : EXTENTION OF 11KV LINE						
Sl. no	Item Code	Item Name	UOM	Quantity	Labour Charges	Total Labour Charges	Load/unload qty	Load/unload charge
1	303201	10 KV 5 kA Lightning Arrester Metal Oxide Ceramic type with GROUND DISCONNECTOR Dwg No. RFSCOM GM QS S 26	No	3.00	78.00	234.00	3.00	0.00
2	302122	11kV Class- HG Fuse Unit with Solid Core Insulators	Set	1.00	155.00	155.00	1.00	0.00
3	279140	Anchor Rod using 12mm rounds/Guy Rod - MS	No	2.00	390.00	780.00	2.00	0.00
4	321437	Distribution Transformer Stacked Core Open Bushing Type for 25kVA Aluminum Wdg Star 1(4 Star)	No	1.00	750.00	750.00	1.00	0.00
5	279112	Double Pole TC Sets for erection of Transformer on RCC/PSC 9 Mtrs Long Poles For 25/63/100kVA 4/5 Star Rated Transformer using 9 Mtr Long RCC Pole	Set	1.00	4,527.00	4,527.00	1.00	0.00
6	301151	For 25 kVA DTC single circuit	Set	1.00	150.00	150.00	1.00	0.00
7	278911	GI Barbed wire (12mtrs/Kg)- Anticlimbing Device	Each	2.00	28.00	56.00	2.00	0.00
8	301107	LT Protection kit	No	1.00	226.00	226.00	1.00	0.00
9	281674	Pipe Grounding-GI Grounding pipe- B - Class- 40mm dia- 2.5mtrs long- 2.9mm thick with bolts nuts-GI Strins and washers complete Minimum Weight of GI	No	3.00	631.00	1,893.00	3.00	0.00
10	200105	RCC Pole - 9 Mtr Long- 145 Kg WL	No	2.00	1,166.00	2,332.00	2.00	0.00
<b>Sub Total</b>					<b>11,103.00</b>			

Estimate Part: C		Estimate Part Description : EXTENTION OF LT LINE						
Sl. no	Item Code	Item Name	UOM	Quantity	Labour Charges	Total Labour Charges	Load/unload qty	Load/unload charge
1	279140	Anchor Rod using 12mm rounds/Guy Rod - MS	No	1.00	390.00	390.00	1.00	0.00
2	279014	LT 4 Pin x Arms MS	No	2.00	106.00	212.00	2.00	0.00
3	200103	RCC Pole 8 Mtr Long 115 Kg	No	1.00	932.00	932.00	1.00	0.00
4	284105	Weasel ACSR	Km	0.04	2,104.00	88.37	0.04	0.00
<b>Sub Total</b>					<b>1,622.37</b>			

Estimate Part: D		Estimate Part Description : DECOMMISSIONING						
Sl. no	Item Code	Item Name	UOM	Quantity	Labour Charges	Total Labour Charges	Load/unload qty	Load/unload charge
1	91270100	Loading of 25 kVA Transformer (when maintenance men for loading and unloading are not available in store)	No	2.00	178.00	356.00	2.00	0.00
2	91210200	For Transporting one pole from 25 to 105Mtrs by Head Load where ever there is no accessibility for transportation by vehicle	per pole	4.00	187.00	748.00	4.00	0.00
3	91260100	Loading and unloading of 8 mtr RCC PSCC poles (loading of poles to vehicles at stores and unloading at worksnot)	No	1.00	69.00	69.00	1.00	0.00
4	91260200	Loading and unloading of 9 mtr RCC PSCC poles (loading of poles to vehicles at stores and unloading at worksnot)	No	3.00	92.00	276.00	3.00	0.00
<b>Sub Total</b>						<b>1,449.00</b>		

<b>Total Labour Charge :</b>	20,192.64
------------------------------	-----------

<b>ESI &amp; PF 17.75% of Labour &amp; loc.Allw</b>	:	3,584.19
<b>CGST 09% of Labour &amp; locality</b>	:	1,817.34
<b>SGST 09% of Labour &amp; locality</b>	:	1,817.34
<b>Total Labour Charges</b>	:	7,218.87

<b>Special Locality Charges</b>	:	0
<b>Break Down Charges</b>	:	0.00
<b>Additional Labour Charges 10% of Total LabourCharges)</b>	:	0.00
<b>Calamity Charges( 45% of Total Labour Charges)</b>	:	0.00
<b>Head Load Charges</b>	:	0
<b>Transportation Cost</b>	:	137.35
<b>Total Other Labour Charges</b>	:	137.35
<b>Grand Total</b>	:	27,548.85

<b>Grand Total in words</b>	:	RUPEES TWENTY-SEVEN THOUSAND FIVE HUNDRED FORTY-NINE ONLY
-----------------------------	---	---

<b>ESI Account No</b>	:	73000352340000999
<b>EMD Reciept Date</b>	:	12/09/1996
<b>EPF Account No</b>	:	KNCKR0037550
<b>EMD Reciept No</b>	:	07971
<b>EMD Amount</b>	:	5,000.00

Asst Executive Engineer(Ele),  
O&M Sub division CESC,  
Nuggehalli

Junior/Asst Engineer(Ele),  
O&M Section,  
HIRISAVE