ಚಾಮುಂಡೇಶ್ವರಿ ವಿದ್ಯುತ್ ಸರಬರಾಜು ನಿಗಮ ನಿಯಮಿತ

(ಕರ್ನಾಟಕ ಸರ್ಕಾರದ ಸ್ವಾಮ್ಯಕೆ ಒಳೆಪಟ್ಟಿದೆ)

ಚಾ.ವಿ.ಸ.ನಿ.ನಿ.,

ಉಪವಿಭಾಗ



CHAMUNDESWARI ELECTRICITY SUPPLY CORPORATION LTD

(A Govt. of Karnataka undertaking)

CESC, Nuggehalli subdivision

Web Site : https://cescmysore.karnataka.gov.in/

RECOMMENDATION FORM FOR AWARDING WORK ON LABOUR CONTRACT

To,

Executive Engineer(Ele), O&M division CESC, Channarayapatna Division

Sir,

Sub : Awarding of work on labor contract basis

Ref : 1814

Ref Date: 17/12/2022

I Wish to recommend for awarding the works detailed here under in favour of **M/s Shivajyothi ElectricalsHanumanthapura (V), Nuggehally (H), Channarayapatna-573131 1CL12819HSN** on labour contract basis as per standard terms and conditions of the Board.

Name of the Work :	:	Replacement and Maintanance

WorkOrder No : M-7717 / 3422322230075 dated 15/12/2022

Work Account Code : 74.5107

Es	Estimate Part: A Estimate Part Description : EXTENTION OF 11KV LINE							
SI. no	ltem Code	Item Name	υом	Quantity	Labour Charges	Total Labour Charges		Load/ unload charge
1	911602003	Straightening of Slant/Bent of RCC Pole of 9 to 10 Itr long in a pit of 1.8 Mtr depth		4.00	647.25	2,589.00	4.00	0.00
2	91050300	Fixing of V-Shape/Horizontal cross arm including Single Top Support Brace and Insulator	each	6.00	122.00	732.00	6.00	0.00
3	91210200	For Transporting one pole from 25 to 105Mtrs by Head Load where ever there is no accessability for transporation by vechicle		¢ 2.00	215.00	430.00	2.00	0.00
4	91260200	Loading and unloading of 9 mtr RCC PSCC poles (loading of poles to vehicles at stores and unloading at workspot)		2.00	106.00	212.00	2.00	0.00
5	200006	D006 PSC Pole - 9 Mtr Long- 200 Kg WL		2.00	1,341.00	2,682.00	2.00	0.00
6	284108	Rabbit ACSR	Km	0.02	3,299.00	65.98	0.02	0.00
7	91060500	Releasing of Rabbit Conductor	r km v	v 2.70	2,969.00	8,016.30	2.70	0.00

8	91020201	Releasing of RCC/PSCC Pole of 9 to 10 Mtr long in a pit of 1.8 Mtr depth		2.00	777.00	1,554.00	2.00	0.00
9	91050301	Releasing of V-Shape/Horizontal cross arm along with Single Top Support Brace and Insulator	Each	6.00	109.80	658.80	6.00	0.00
10	281683	Spiral Earth Electrode	No	2.00	70.00	140.00	2.00	0.00
11	91051700	Stringing of conductor Rabbit ACSR binding of conductor on each insulator and dead ending on strain or disc/strain insulator by means of clamps.	r KM/\	N 2.70	3,299.00	8,907.30	2.70	0.00
	Sub Total					25,987.38		

Total Labour Charge :

25,987.38

ESI & PF 17.75% of Labour & loc.Allw	:	4,612.76
CGST 09% of Labour & locality	:	2,338.86
SGST 09% of Labour & locality	:	2,338.86
Total Labour Charges	:	9,290.49

Special Locality Charges	:	0
Break Down Charges	:	0.00
Additional Labour Charges 10% of Total LabourCharges)	:	0.00
Calamity Charges(45% of Total Labour Charges)	:	0.00
Head Load Charges		0
Transportation Cost	:	211.68
Total Other Labour Charges	:	211.68
Grand Total		35,489.55
Grand Total in words	:	RUPEES THIRTY-FIVE THOUSAND FOUR HUNDRED NINETY ONLY

ESI Account No :	73000367200000999
EMD Reciept Date :	21/06/2012
EPF Account No :	KNCKR1374173
EMD Reciept No :	4221000029596
EMD Amount :	5,000.00

Asst Executive Engineer(Ele), O&M Sub division CESC, Nuggehalli Junior/Asst Engineer(Ele), O&M Section, HIRISAVE