

ಚಾಮುಂಡೇಶ್ವರಿ ವಿದ್ಯುತ್ ಸರಬರಾಜು ನಿಗಮ ನಿಯಮಿತ

(ಕರ್ನಾಟಕ ಸರ್ಕಾರದ ಸ್ವಾಮ್ಯಕ್ಕೆ ಒಳಪಟ್ಟಿದೆ)

ಚಾ.ವಿ.ಸ.ನಿ.ನಿ.,

ಉಪವಿಭಾಗ



CHAMUNDESWARI ELECTRICITY
SUPPLY CORPORATION LTD

(A Govt. of Karnataka undertaking)

CESC, Channarayapatna subdivision

Web Site : <https://cescmysore.karnataka.gov.in/>

RECOMMENDATION FORM FOR AWARDING WORK ON LABOUR CONTRACT

To,

Executive Engineer(Ele),
O&M division CESC,
Channarayapatna Division

Sir,

Sub : Awarding of work on labor contract basis

Ref : 3356

Ref Date: 31/10/2022

I Wish to recommend for awarding the works detailed here under in favour of **M/s Swathi Electricals No 295, Mylaralinga Temple, Gollara Street, Kote, Channarayapatna-573116 1CL00875HSN** on labour contract basis as per standard terms and conditions of the Board.

Name of the Work : Replacement and Maintenance
WorkOrder No : M-7865 / 3421522230056 dated 27/10/2022
Work Account Code : 74.5107

Estimate Part: A		Estimate Part Description : EXTENTION OF 11KV LINE						
Sl. no	Item Code	Item Name	UOM	Quantity	Labour Charges	Total Labour Charges	Load/unload qty	Load/unload charge
1	279140	Anchor Rod using 12mm rounds/Guy Rod - MS	No	5.00	448.00	2,240.00	5.00	0.00
2	91020300	Erection of RCC PCC PSC poles of 7 5 to 8 mtr long in pit of 1 5 mtr depth	No	2.00	1,214.00	2,428.00	2.00	0.00
3	91050300	Fixing of V-Shape/Horizontal cross arm including Single Top Support Brace and Insulator	each	8.00	122.00	976.00	8.00	0.00
4	91210200	For Transporting one pole from 25 to 105Mtrs by Head Load where ever there is no accessability for transporation by vechicle	per pole	4.00	215.00	860.00	4.00	0.00
5	91260200	Loading and unloading of 9 mtr RCC PSC poles (loading of poles to vehicles at stores and unloading at worksnot)	No	4.00	106.00	424.00	4.00	0.00
6	200006	PSC Pole - 9 Mtr Long- 200 Kg WL	No	1.00	1,341.00	1,341.00	1.00	0.00
7	284108	Rabbit ACSR	Km	0.05	3,299.00	164.95	0.05	0.00

8	200105	RCC Pole - 9 Mtr Long- 145 Kg WL	No	3.00	1,341.00	4,023.00	3.00	0.00	
9	91060800	Releasing and Refixing of over head service mains (single phase 3 phase) (While executing reconductoring works only) Per connection installation	r km w	6.00	67.00	402.00	6.00	0.00	
10	91060500	Releasing of Rabbit Conductor	r km w	0.36	2,969.00	1,068.84	0.36	0.00	
11	91020201	Releasing of RCC/PSCC Pole of 9 to 10 Mtr long in a pit of 1.8 Mtr depth	No	2.00	777.00	1,554.00	2.00	0.00	
12	91050301	Releasing of V-Shape/Horizontal cross arm along with Single Top Support Brace and Insulator	Each	8.00	109.80	878.40	8.00	0.00	
13	91060400	Releasing of Weasel Conductor	r km w	0.43	2,178.00	936.54	0.43	0.00	
14	281683	Spiral Earth Electrode	No	2.00	70.00	140.00	2.00	0.00	
15	91051700	Stringing of conductor Rabbit ACSR binding of conductor on each insulator and dead ending on strain or disc/strain insulator by means of clamps.	r KM/W	0.36	3,299.00	1,187.64	0.36	0.00	
16	91051600	Stringing of conductor Squirrel Weasel binding of conductor on each insulator and dead ending on strain or disc/strain insulator by means of clamps.	r KM/W	0.43	2,420.00	1,040.60	0.43	0.00	
17	284105	Weasel ACSR	Km	0.03	2,420.00	72.60	0.03	0.00	
Sub Total					19,737.57				

Total Labour Charge :	19,737.57
------------------------------	------------------

ESI & PF 17.75% of Labour & loc.Allw	:	3,503.42
CGST 09% of Labour & locality	:	1,776.38
SGST 09% of Labour & locality	:	1,776.38
Total Labour Charges	:	7,056.18

Special Locality Charges	:	0
Break Down Charges	:	0.00
Additional Labour Charges 10% of Total LabourCharges)	:	0.00
Calamity Charges(45% of Total Labour Charges)	:	0.00
Head Load Charges	:	0
Transportation Cost	:	749.14
Total Other Labour Charges	:	749.14
Grand Total	:	27,542.89

Grand Total in words	:	RUPEES TWENTY-SEVEN THOUSAND FIVE HUNDRED FORTY-THREE ONLY
-----------------------------	---	--

ESI Account No	:	1460220
EMD Reciept Date	:	25/02/2016
EPF Account No	:	KNCKR1460220
EMD Reciept No	:	4210100065899
EMD Amount	:	5,000.00

Asst Executive Engineer(Ele),
O&M Sub division CESC,
Channarayapatna

Junior/Asst Engineer(Ele),
O&M Section,
KUNDURU MATA