

ಚಾಮುಂಡೇಶ್ವರಿ ವಿದ್ಯುತ್ ಸರಬರಾಜು ನಿಗಮ ನಿಯಮಿತ

( ಕರ್ನಾಟಕ ಸರ್ಕಾರದ ಸ್ವಾಮ್ಯಕ್ಕೆ ಒಳಪಟ್ಟಿದೆ )

ಚಾ.ವಿ.ಸ.ನಿ.ನಿ.,

ಉಪವಿಭಾಗ



CHAMUNDESWARI ELECTRICITY  
SUPPLY CORPORATION LTD

(A Govt. of Karnataka undertaking )

CESC, Nuggehalli subdivision

Web Site : <https://cescmysore.karnataka.gov.in/>

RECOMMENDATION FORM FOR AWARDING WORK ON LABOUR CONTRACT

To,

Executive Engineer(Ele),  
O&M division CESC,  
Channarayapatna Division

Sir,

**Sub : Awarding of work on labor contract basis**

Ref : 7867-01

Ref Date: 15/12/2022

I Wish to recommend for awarding the works detailed here under in favour of **M/s Sri Vinayaka ElectricalsHonnamaranahally(V), Jamburu(P), Nuggehalli(H), Channarayapatna-573131 1CL07828HSN** on labour contract basis as per standard terms and conditions of the Board.

**Name of the Work :** Replacement and Maintenance

**WorkOrder No :** L-7867 / 3422121220070 dated 25/11/2021

**Work Account Code :** 74.5107

Estimate Part: A		Estimate Part Description : ERECTION OF TRANSFORMER						
Sl. no	Item Code	Item Name	UOM	Quantity	Labour Charges	Total Labour Charges	Load/unload qty	Load/unload charge
1	302122	11kV Class- HG Fuse Unit with Solid Core Insulators	Set	1.00	155.00	155.00	1.00	0.00
2	279140	Anchor Rod using 12mm rounds/Guy Rod - MS	No	2.00	390.00	780.00	2.00	0.00
3	279112	Double Pole TC Sets for erection of Transformer on RCC/PSC 9 Mtrs Long Poles For 25/63/100kVA 4/5 Star Rated Transformer using 9 Mtr Long RCC Pole	Set	1.00	4,527.00	4,527.00	1.00	0.00
4	279014	LT 4 Pin x Arms MS	No	3.00	106.00	318.00	3.00	0.00
5	301107	LT Protection kit	No	1.00	226.00	226.00	1.00	0.00
6	281674	Pipe Grounding-GI Grounding pipe- B - Class- 40mm dia- 2.5mtrs long- 2.9mm thick with bolts nuts-GI Strips and washers complete Minimum Weight of GI	No	3.00	631.00	1,893.00	3.00	0.00
7	99990663	Rabbit ACSR Conductor Release good	Mtr	20.00	2.87	57.38	0.02	0.00

8	200105	RCC Pole - 9 Mtr Long- 145 Kg WL	No	2.00	1,166.00	2,332.00	2.00	0.00
9	284105	Weasel ACSR	Km	0.02	2,104.00	42.08	0.02	0.00
<b>Sub Total</b>						<b>10,330.46</b>		

<b>Total Labour Charge :</b>	<b>10,330.46</b>
------------------------------	------------------

<b>ESI &amp; PF 17.75% of Labour &amp; loc.Allw</b>	:	1,833.66
<b>CGST 09% of Labour &amp; locality</b>	:	929.74
<b>SGST 09% of Labour &amp; locality</b>	:	929.74
<b>Total Labour Charges</b>	:	<b>3,693.14</b>

<b>Special Locality Charges</b>	:	0
<b>Break Down Charges</b>	:	0.00
<b>Additional Labour Charges 10% of Total LabourCharges)</b>	:	0.00
<b>Calamity Charges( 45% of Total Labour Charges)</b>	:	0.00
<b>Head Load Charges</b>	:	0
<b>Transportation Cost</b>	:	793.65
<b>Total Other Labour Charges</b>	:	<b>793.65</b>
<b>Grand Total</b>	:	<b>14,817.25</b>

<b>Grand Total in words</b>	:	<b>RUPEES FOURTEEN THOUSAND EIGHT HUNDRED SEVENTEEN ONLY</b>
-----------------------------	---	--

<b>ESI Account No</b>	:	1387420
<b>EMD Reciept Date</b>	:	18/07/2001
<b>EPF Account No</b>	:	KNCKR1387420
<b>EMD Reciept No</b>	:	021457
<b>EMD Amount</b>	:	5,000.00

Asst Executive Engineer(Ele),  
O&M Sub division CESC,  
Nuggehalli

Junior/Asst Engineer(Ele),  
O&M Section,  
NUGGEHALLY