

ಚಾಮುಂಡೇಶ್ವರಿ ವಿದ್ಯುತ್ ಸರಬರಾಜು ನಿಗಮ ನಿಯಮಿತ

(ಕರ್ನಾಟಕ ಸರ್ಕಾರದ ಸ್ವಾಮ್ಯಕ್ಕೆ ಒಳಪಟ್ಟಿದೆ)

ಚಾ.ವಿ.ಸ.ನಿ.ನಿ.,

ಉಪವಿಭಾಗ



CHAMUNDESWARI ELECTRICITY
SUPPLY CORPORATION LTD

(A Govt. of Karnataka undertaking)

CESC, Nuggahalli subdivision

Web Site : <https://cescmysore.karnataka.gov.in/>

RECOMMENDATION FORM FOR AWARDING WORK ON LABOUR CONTRACT

To,

Executive Engineer(Ele),
O&M division CESC,
Channarayapatna Division

Sir,

Sub : Awarding of work on labor contract basis

Ref : 6722-26B

Ref Date: 12/12/2022

I Wish to recommend for awarding the works detailed here under in favour of **M/s Ravi Electricals And Electronics No-3, Nethaji Road, Kolda Street, Kote, Channarayapatna-573116 1CL00214HSN** on labour contract basis as per standard terms and conditions of the Board.

Name of the Work : Replacement and Maintanance
WorkOrder No : M-7934 / 3422522230066 dated 30/11/2022
Work Account Code : 74.5107

Estimate Part: A		Estimate Part Description : EXTENTION OF LT LINE						
Sl. no	Item Code	Item Name	UOM	Quantity	Labour Charges	Total Labour Charges	Load/unload qty	Load/unload charge
1	279140	Anchor Rod using 12mm rounds/Guy Rod - MS	No	5.00	448.00	2,240.00	5.00	0.00
2	91050200	Fixing of 4 Pin cross arm with Insulator and Braces	each	8.00	122.00	976.00	8.00	0.00
3	91210200	For Transporting one pole from 25 to 105Mtrs by Head Load where ever there is no accessability for transporation hv vechicle	per pole	9.00	215.00	1,935.00	9.00	0.00
4	91260100	Loading and unloading of 8 mtr RCC PSCC poles (loading of poles to vehicles at stores and unloading at worksnot)	No	9.00	79.00	711.00	9.00	0.00
5	200004	PSC Pole - 8 Mtr Long- 200 Kg WL	No	1.00	1,072.00	1,072.00	1.00	0.00
6	284108	Rabbit ACSR	Km	0.05	3,299.00	164.95	0.05	0.00
7	200103	RCC Pole 8 Mtr Long 115 Kg	No	4.00	1,072.00	4,288.00	4.00	0.00

8	91060800	Releasing and Refixing of over head service mains (single phase 3 phase) (While executing reconductorina works only) Per connection installation	r km w	8.00	67.00	536.00	8.00	0.00
9	91050201	Releasing of 4 Pin cross arm along with Insulator and Braces	Each	8.00	109.80	878.40	8.00	0.00
10	91020101	Releasing of RCC/PSCC Pole of 7.5 to 8 Mtr long in a pit of 1.5 Mtr depth	No	5.00	619.00	3,095.00	5.00	0.00
11	91060400	Releasing of Weasel Conductor	r km w	1.80	2,178.00	3,920.40	1.80	0.00
12	91051600	Stringing of conductor Squirrel Weasel binding of conductor on each insulator and dead ending on strain or disc/strain insulator by means of clamps	r KM/W	1.80	2,420.00	4,356.00	1.80	0.00
Sub Total					24,172.75			

Total Labour Charge :	24,172.75
------------------------------	------------------

ESI & PF 17.75% of Labour & loc.Allw	:	4,290.66
CGST 09% of Labour & locality	:	2,175.55
SGST 09% of Labour & locality	:	2,175.55
Total Labour Charges	:	8,641.76

Special Locality Charges	:	0
Break Down Charges	:	0.00
Additional Labour Charges 10% of Total LabourCharges)	:	0.00
Calamity Charges(45% of Total Labour Charges)	:	0.00
Head Load Charges	:	0
Transportation Cost	:	645.60
Total Other Labour Charges	:	645.60
Grand Total	:	33,460.11

Grand Total in words	:	RUPEES THIRTY-THREE THOUSAND FOUR HUNDRED SIXTY ONLY
-----------------------------	---	---

ESI Account No	:	73000367190000999
EMD Reciept Date	:	20/08/2008
EPF Account No	:	KNCKR1356311
EMD Reciept No	:	09952
EMD Amount	:	5,000.00

Asst Executive Engineer(Ele),
O&M Sub division CESC,
Nuggehalli

Junior/Asst Engineer(Ele),
O&M Section,
DIDAGA