



RECOMMENDATION FORM FOR AWARDING WORK ON LABOUR CONTRACT

To,
Executive Engineer(Ele),
O&M division CESC,
Hunsur Division

Sir,

Sub : Awarding of work on labor contract basis

Ref : 001

Ref Date: 18/11/2022

I Wish to recommend for awarding the works detailed here under in favour of **Sri Lakshmi Venkateshwara**
Electricals Singaramaranahalli village, Bilikere Hobali, Hunsur Taluq 1CL02885MYS on labour contract basis as per
standard terms and conditions of the Board.

Name of the Work : Service Connection

WorkOrder No : M-5531 / 3145222230052 dated 26/07/2022

Work Account Code : 14.4007

Estimate Part: A		Estimate Part Description : ERECTION OF TRANSFORMER						
Sl. no	Item Code	Item Name	UOM	Quantity	Labour Charges	Total Labour Charges	Load/unload qty	Load/unload charge
1	91260300	Loading and unloading of 8 mtr PSCC pole (140Kg WL) poles (loading of poles to vehicles at stores and unloading at worksnt)	No	1.00	67.00	67.00	1.00	0.00
2	303201	10 KV 5 kA Lightning Arrester Metal Oxide Ceramic type with GROUND DISCONNECTOR Dwg No. RESCOM GM OS S 26	No	3.00	90.00	270.00	3.00	0.00
3	304212	11KV 200Amps Single Break GOS	set	1.00	805.00	805.00	1.00	0.00
4	302122	11KV Class- HG Fuse Unit with Solid Core Insulators	Set	1.00	178.00	178.00	1.00	0.00
5	279020	11KV Horizontal X Arms Mild Steel(MS)	No	18.00	122.00	2,196.00	18.00	0.00
6	279140	Anchor Rod using 12mm rounds/Guy Rod - MS	No	7.00	448.00	3,136.00	7.00	0.00
7	613050	Caution/Danger Board	No	1.00	61.00	61.00	1.00	0.00

8	321437	Distribution Transformer Stacked Core Open Bushing Type for 25kVA Aluminum Wdg Star 1(4 Star)	No	1.00	863.00	863.00	1.00	0.00
9	279111	Double Pole TC Sets for erection of Transformer on RCC/PSC 9 Mtrs Long Poles For 25/63/100kVA 4/5 Star Rated Transformer on 9 Mtr Long PSC 300kg Wl	Set	1.00	2,623.00	2,623.00	1.00	0.00
10	279112	Double Pole TC Sets for erection of Transformer on RCC/PSC 9 Mtrs Long Poles For 25/63/100kVA 4/5 Star Rated Transformer using 9 Mtr Long RCC Pole	Set	1.00	2,623.00	2,623.00	1.00	0.00
11	279092	HT ST Support 50x6mm Flat - MS	No	18.00	81.00	1,458.00	18.00	0.00
12	91260200	Loading and unloading of 9 mtr RCC PSC poles (loading of poles to vehicles at stores and unloading at workspot)	No	4.00	106.00	424.00	4.00	0.00
13	279014	LT 4 Pin x Arms MS	No	2.00	122.00	244.00	2.00	0.00
14	301107	LT Protection kit	No	1.00	260.00	260.00	1.00	0.00
15	284108	Rabbit ACSR	Km	0.52	3,299.00	1,705.58	0.52	0.00
16	200105	RCC Pole - 9 Mtr Long- 145 Kg WL	No	4.00	1,341.00	5,364.00	4.00	0.00
17	200103	RCC Pole 8 Mtr Long 115 Kg	No	1.00	1,072.00	1,072.00	1.00	0.00
18	281683	Spiral Earth Electrode	No	2.00	70.00	140.00	2.00	0.00
19	284105	Weasel ACSR	Km	0.04	2,420.00	96.80	0.04	0.00
Sub Total						23,586.38		

Total Labour Charge :	23,586.38
------------------------------	------------------

ESI & PF 17.75% of Labour & loc.Allw	:	4,186.58
CGST 09% of Labour & locality	:	2,122.77
SGST 09% of Labour & locality	:	2,122.77
Total Labour Charges	:	8,432.13

Special Locality Charges	:	7075.91
Break Down Charges	:	0.00
Additional Labour Charges 10% of Total LabourCharges)	:	0.00
Calamity Charges(45% of Total Labour Charges)	:	0.00
Head Load Charges	:	0
Transportation Cost	:	4,955.92
Total Other Labour Charges	:	12,031.83
Grand Total	:	44,050.34

Grand Total in words	:	RUPEES FORTY-FOUR THOUSAND FIFTY ONLY
-----------------------------	---	--

ESI Account No	:	AAA
EMD Reciept Date	:	08/08/2007
EPF Account No	:	AAA
EMD Reciept No	:	02023
EMD Amount	:	5,000.00

[Signature]
Asst Executive Engineer(Ele),
O&M Sub division CESC,
Bilikere

[Signature]
Junior/Asst Engineer(Ele),
O&M Section,
K.S.GADDIGE